

CITY OF DE PERE

Engineering

925 S. Sixth Street, De Pere, WI 54115 | 920-339-4061 | www.de-pere.org



May 29, 2019

ADDENDUM NO. 1
PROJECT 19-11
GARRITY'S GLEN SOUTH SUBDIVISION CONSTRUCTION

TO: Prospective Bidders

FROM: City of De Pere

Notice is hereby given that the contract documents for the Project 19-11 are amended as hereinafter set forth. If you will be submitting a bid for Project 19-11, you must sign this addendum and include it with your submittal.

This addendum consists of 3 pages.

CHANGES TO GENERAL REQUIREMENTS

- Under Section 01 10 00, Summary of Work, 1.9 insert the following:
 - The anticipated cut/fill volume for the site is per the table below.

Location	Cut (CY)	Fill (CY)	Net (CY)
Garroman Drive	1229	3880	-2651
Ballyvaughan Road	793	6395	-5602
Tipperary (E-W)	5	3115	-3110
Tipperary (N-S)	4	4884	-4880
Kilrush (E-W)	18	2896	-2878
Kilrush (N-S)	1628	925	703
Lawrence Drive	17	1475	-1458
Fill (Between Ballyvaughan and Tipperary)	0	11974	-11974
Pond (Per Bid Item)	32500		32500

G. Excess fill from the pond and street construction may be placed in the lots between Ballyvaughan Road and Tipperary Trail by spreading uniformly over the area prior to placing topsoil, seed, and mulch. Restoration in this area is part of the unit price bid for Landscaping-Topsoil, Temporary Nurse Crop, and Mulch.

H. Excess fill from utility trenches may be placed in other areas within the subdivision as shown on the sheet named "Potential Locations for Trench Spoils" or removed from the site. These areas shall be restored with topsoil, temporary nurse crop, and mulch. The cost for stripping topsoil and restoration for areas where trench spoils are placed shall not be paid. If this option of leaving the material on site is chosen, fill shall begin at the edge of the utility trench and taper down to the existing ground at a uniform slope approved by the Engineer.

I. Depending on when pond grading is completed, a temporary swale may be required to drain the storm sewer off of Garroman Drive to the existing ponds to the north.

CHANGES TO PLANS

1. On Page G001, Title Sheet update the tables as follows:
 - a. Insert "C421" and "Potential Locations for Trench Spoils"
2. Insert attached Sheet C421, Potential Locations for Trench Spoils into the plan set.

Sincerely,

DEPARTMENT OF PUBLIC WORKS



Eric P. Rakers, P.E.
City Engineer



Acknowledged by: _____ Date: _____



CITY OF DE PERE

ENGINEERING DIVISION 925 S. SIXTH ST DE PERE WI 54115
OFFICE 920-339-4061 FAX 920-339-4071

GARRITY'S GLEN SOUTH
POTENTIAL LOCATIONS FOR TRENCH SPOILS

NAME: GARRITY'S GLEN SOUTH
SUBDIVISION CONSTRUCTION
PROJECT # 19-11

	BY	DATE
SURVEYED	MACH IV	8-2018
DRAWN	SRL	5-2019
DESIGNED	SRL	5-2019
CHECKED	SRL	5-2019

REVISIONS / ISSUES			
NO.	DATE	BY	REMARKS